

REBOUND HAMMER TEST REPORT

ವಿಷಯ : ಕಲಬುರಗಿ ತಾಲೂಕಿನ ವೇದಾ ಪಬ್ಲಿಕ್ ಆಂಗ್ಲ ಮಾಧ್ಯಮ ಶಾಲೆ ಸರ್ವೆ ನಂ.105/10 ಆಜಾದ್ ನಗರ
ಕೆ.ಎ.ಬಿ.ಸ್ಟೇಷನ್ ಹತ್ತಿರ ಸೇಡಂ ರಸ್ತೆ ಕಲಬುರಗಿ, ಶ್ರೀ ಬಸವಣ್ಣ ಎಜುಕೇಷನ್ & ಚಾರಿಟೇಬಲ್ ಟ್ರಸ್ಟ್
ಅಡಿಯಲ್ಲಿ ನಡೆಯುತ್ತಿರುವ VEDAA PUBLIC SCHOOL Kalaburagi, ಕಟ್ಟಡಸುರಕ್ಷತಾ ವರದಿ.
ಉಲ್ಲೇಖ:- 1) ಸಹಾಯಕ ಕಾರ್ಯನಿರ್ವಾಹಕ ಇಂಜಿನಿಯರರು, ಲೋ.ಇ. ಉಪ ವಿಭಾಗ ಕಲಬುರಗಿ ರವರ ಪತ್ರ
ಸಂಖ್ಯೆ.1066 ದಿನಾಂಕ: 13-08-2026.

2) Section Officer, Office of the Asst. Executive Engineer PWD QA Sub-Division;
Kalaburagi, Site Inspection on Dated: 19-08-2026.

Date of Testing : 19-08-2026.

ಕ್ರ.ಸಂ	ಕಲಸದ ಅಂಶ	(ರಿಬೌಂಡ್ ಹ್ಯಾಮರ್) Reading/ Value	(ರಿಬೌಂಡ್ ಹ್ಯಾಮರ್‌ನಿಂದ) Achieved Strength N/mm ²	(ರಿಬೌಂಡ್ ಹ್ಯಾಮರ್‌ನಿಂದ) Achieved Strength Avg N/mm ²
				05
01	02	03	04	
1	Ground floor Column	32 30 29 30 29 29	26.90 23.60 22.10 23.60 22.10 22.10	23.40
2	1 st floor Column	28 30 32 30 28 30	20.60 23.60 26.90 23.60 20.60 23.60	23.15
3	1 st floor Slab	26 28 26 24 30 26	22.10 25.20 22.10 19.10 28.50 22.10	23.18

Note :- 1. The test results relate to the sample tested & shall not be reproduced in part.
2. Materials need to be tested as per frequency of IS Code.
3. Compressive strength arrived by the Rebound Hammer is an indicative strength.
Test charges ರೂ.300*3(900)+162(ಜಿ.ಎಸ್.ಟಿ.)= 1062.00


Asst. / Junior Engineer


Assistant Executive Engineer
PWD QA sub- Divn, Kalaburagi.